



Phone. No. (02164) 272414, 8275706613
Web : <http://gcekarad.ac.in>
Email: principal@gcekarad.ac.in,
principal.gcekarad@dtmaharashtra.gov.in

Govt. of Maharashtra
**GOVT. COLLEGE OF ENGINEERING,
KARAD**
(An Autonomous Institute of Govt. of Maharashtra)
Vidyanagar, Karad -415124 Dist.- Satara

GCEK/QUOT/Fixing Paving Blocks/2021-22/571

Date:- 4 FEB 2022

To,

**Sub: - Fixing of paving blocks at main entrance garden and in front of Dean Academics at
GCE**

Dear Sir,

With reference to the above, I request you to please quote your most comparative rates for the work as detailed overleaf/enclosed so as to reach the office **on or before 22/02/2022**. The prices of the **work should be quoted F.O.R. at G.C.E., KARAD** and exclusive of all taxes. The delivery period should be stated clearly and adhered to 'AF' or 'D' forms will be supplied where necessary. The R.R. through Bank or V.P. will not be accepted if order is placed. The specification of the material should be mentioned in full such as brand, make and company etc. I do not bind myself to accept/reject the offer, and its detailed leaflet must be attached. Your quotation should be valid at least for 30 days from the date of opening. The quotations should be sent in a sealed envelope. The envelope should please be superscripted with words **'QUOTATION DUE ON – Principal, Govt. College of Engg. Karad'**

With this office reference no. & date of opening should also be mentioned on the sealed envelope. If the materials are not supplied according to the specification, it will be returned to you at your own cost. If ordered, you will have to submit three copies of the bill, which will be passed after receipt of material in good condition. Please note that if there is any overwriting in the quotation, the said item will not be taken in to consideration unless is initialed.

Government registered contractors are only eligible to fill the quotations.

The quotations should be received on or before: - 22/02/2022 on or before 4:00 pm.

The quotation received will be opened on: - 22/02/2022, at 11.00 am.

‘QUOTATION – Principal, Govt. College of Engg. Karad’

Name of Work: - Fixing of paving blocks at main entrance garden and in front of Dean Academics at GCE


SUMMARY SHEET

| Sr. No. | Description | Amount |
|---------|-------------------------|------------------------|
| | Total Civil Work | Rs. 1,80,048.00 |
| | Add GST 12% | Rs. 21,606.00 |
| | Total with GST | Rs. 2,01,654.00 |

ABSTRACT (As per SSR 2021-22)

| Sr. No. | Item Ref. | Item Description | Qty | Unit | Rate in Rupees | Amount |
|---------|----------------------|--|--------|------|----------------|----------|
| 1 | 46.19 Pg. No. 215 | Removing cement tiles, or marble or polished shahabad floor or dado without bed concrete including stacking the materials as directed with all leads, lifts etc. complete | 121.72 | Sqm | 42.00 | 5112.24 |
| 2 | 21.01 Pg. No. 115 | Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.50 m.) By Manual Means | 12.55 | Cum | 232.00 | 2911.60 |
| 3 | 21.37 Pg. No. 117 | Filling in plinth and floors with contractors material/brought from outside and approved by Engineer incharge in layers of 15 cm to 20 cm including watering and compaction etc. complete. | 12.17 | Cum | 550.00 | 6693.50 |
| 4 | 2.31 Pg. No. 24 | Compacting the hard murum side widths including laying in layers on each side with vibratory roller including artificial watering etc. complete. | 220.80 | Sqm | 19.00 | 4195.20 |
| 5 | 27.12 Pg. No. 144 | Providing fly ash brick masonry with conventional/ I.S. type fly ash bricks in C.M. 1:6 in foundation and plinth including bailing out water manually striking joints, racking out joints watering and scaffolding etc. complete. Completed Item Rate = 6762/ Cum Fly Ash Brick = (500 x 7) = 3500/ Cum Total Rate without brick = 3262/ Cum | 7.60 | Cum | 3262.00 | 24791.20 |
| 6 | 32.11 Pg. No. 153 | Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1 Kilogram per cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc.complete. | 42.58 | Sqm | 599.00 | 25505.42 |

| Sr. No. | Item Ref. | Item Description | Qty | Unit | Rate in Rupees | Amount |
|---------|------------------|---|--------|------|----------------|------------------|
| 7 | 33.53Pg. No. 160 | Providing and fixing heavy duty inter locking concrete RUBBER MOULD GLOSSY PAVING BLOCKS of 60 millimeter thickness of having a strength of 400 Kilogram/sq.m of approved quality and shape on a bed of crushed sand of 25 to 30 millimeter thick including striking joints and cleaning etc. complete. (using 100% crushed sand)Completed Item Rate = 923/ SqmPaving block material rate = 614/ SqmTotal Rate without block = 309/ Cum | 342.52 | Sqm | 309.00 | 105838.68 |
| 8 | | Other repairs works if any | | LS | | 5000.00 |
| | | | | | | |
| | | TOTAL AMOUNT | | | | 180047.84 |
| | | SAY | | | | 180048.00 |


Principal
Govt. College of Engineering, Karad.